KOLAR DIVISION.

Notice, dated 6th March 1897.

It is hereby notified that a sum of Rs. 15-5-8, due to late contractor Vahab Alli for work done on Byadabale tank, Bowringpet taluk, has been placed in the Savings Bank. Any legal heirs of the deceased contractor, with a claim certificate, may apply to the Executive Engineer., Kolar division, for receiving the above sum within three months from this date; failing which, the amount will be forfeited to Government.

V. ARUNACHELLA MUDALIAR, *Exec. Engineer.*

BANGALORE DIVISION.

The 27th March 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore division, up to 2 P. M. on 26th April 1897, for constructing the Administrative Block of the General Hospital at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 12 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (1,000) one thousand in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the Administrative Block of the General Hospital at Bangalore"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7 The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

N. B.—Two separate tenders should be submitted for the work, one for building the walls with stone and the other with brick masonry; in default of which, tenders will not be taken notice of.

CONSTRUCTING ADMINISTRATIVE BLOCK OF THE GENERAL HOSPITAL AT BANGALORE.

Items of work.	*Per.*	*Lower storey.*	*Upper storey.*
Earthwork (excavating foundation)	C. yds.	1,906	..
Do (filling in basement)	Do	1,015	..
Concrete under foundation	C. ft.	17,255	..
Stone in chunam do	Do	22,361	..
Do basement	Do	16,949	..
Brick in chunam superstructure	Do	51,203	..
Do do	Do	..	45,208
Do semi-circular archwork	Do	5,257	1,045
Relieving and flat arch work	Do	..	3,498
Plastering with chunam	Sqr.	..	549·77
Do do	Do	387·20	..
Cuddappah slab flooring over concrete	Do	34·38	..
Venetian mosaic tiles flooring with borders, complete	Do	14·25	..
Mangalore tiles flooring including pointing with cement ..	Do	52 92	..
Paving with stone slabs to bath, &c.	Do	8·06	..
Terrace floor with special tiles	Do	18 03	..
Terrace flooring 9" thick	Do	50·99	..
Do with Mangalore tiles	Do	37·52	..
Steel girders	C. ft.	132⅓	323
Teakwood work including oiling	C. ft.	2,822	4,895
Doors and windows without fanlight	S. ft.	848	..
Do with do	Do	2,074	..
Do do ventilators	Do	..	4,384